ICE PRODUCTION OF 6 TO 12 TONS/DAY

QUALTY ICE FROM THE ICELINGS P119F TUBE—ICE MACHINE IS TRANSPORTED EFFICIENTLY TO OUR BULK ICE STORAGE BIN BY OUR SCREW CONVEYOR SYSTEM. ICE IS FED DIRECTLY FROM THE BIN BY THE BAGGER WHERE A MEASURED VOLUME OF ICE IS AUTOMATICALLY DISPENSED INTO AN OPEN POLY ICE BAG. AN OPERATOR SIMPLY TRANFERS THE POLY BAG OF ICE TO THE BAG SEALER TO WHERE IT IS SECURELY SEALED. THE BELT CONVEYOR CONVENIENTLY CARRIES THE FINISHED BAG OF ICE AWAY TO THE SECOND OPERATOR WHO REMOVES IT FROM THE BELT CONVEYOR AND PLACES IT ON A PALLET. THE FULL PALLET OF ICE IS TRANSFERRED TO THE COLD STORAGE OR DIRECTLY INTO THE DELIVERY TRUCK.

APPROX. PLANT AREA REQUIRED = 900 sq. ft

ALL DIMENSIONS. ARE IN FEET

CLIENT : PRAG, DELHI					
CONSULTANTS : CHIRAG ICE FACTORY PVT LTD					
SCALE TRUE SCALE QTY.	6-12 TON PLANT LAYOUT	DRG. NO	YOUT/	/0CT1/	[/] 06–07
	L HIRAG ICE FACTORY PVT.LTD. ANUFACTURER OF REFRIGRN & ENGG EOPT	REV.	0	1	
ICELINGS D	D-29/12, TURBHE MIDC, NAVI MUMBAI -400 705. TEL: - 91-22-2763 1378/6513 1986 FAX-2761 4801(EXTN. 22) E-MAIL: RUSTOM@ICELINGS.COM	PREPARED CHECKED			
F		APPROVED			